| Project Title:        | CTH I, Mukwonago River Bridge | Project #:    | 202203          |
|-----------------------|-------------------------------|---------------|-----------------|
| Department:           | Public Works - Highways       | Project Type: | Rehabilitation  |
| Phase:                | Preliminary Design            | Road Name:    | Beloit Road     |
| <b>Budget Action:</b> | C - Scope C - \$ Update       | Manager:      | Allison Bussler |
| Date:                 | July 3, 2024                  | Map / Image:  | Click Here      |

| Year                             | 2022        | 2023-24    | 2025           | 2026       | 2027       | Total      |
|----------------------------------|-------------|------------|----------------|------------|------------|------------|
| Project Phase                    | Pre. Design |            | Design         | Land       | Const      | Project    |
|                                  |             |            |                |            |            |            |
| Expenditure Budget               | \$6,000     | \$0        | \$23,000       | \$45,000   | \$98,000   | \$172,000  |
| Revenue Budget                   | <u>\$0</u>  | <u>\$0</u> | <u>\$0</u>     | <u>\$0</u> | <u>\$0</u> | <u>\$0</u> |
| Net Costs After Revenues Applied | \$6,000     | \$0        | \$23,000       | \$45,000   | \$98,000   | \$172,000  |
| COST DOCUMENTATION               |             |            | REVENUE        |            |            |            |
| Preliminary Design               |             | \$6,000    |                |            |            |            |
| Design                           |             | \$95,000   | Fed Aid Bridge | \$484,000  |            |            |
| WisDOT Design Review             |             | \$20,000   |                |            |            |            |
| Land Acquisition                 |             | \$45,000   |                |            |            |            |
| Construction                     |             | \$383,000  |                |            |            |            |
| Construction Management          |             | \$88,000   |                |            |            |            |
| Contingency                      | _           | \$19,000   |                |            | _          |            |
| Total Project Cost               |             | \$656,000  | Total Revenue  |            |            | \$484,000  |
| EXPENDITURE BUDGET               |             | \$172,000  | REVENUE BUD    | GET        |            | \$0        |

Project Scope & Description: This rehabilitation of the CTH I bridge over the Mukwonago River is rescoped from concrete overlay to concrete deck repairs. The spalls and delaminations in the deck will be repaired with concrete patching, using sacrificial anodes. Concrete repairs will be made to the spalled slab edges. Galvanized steel flashing will be installed on the slab edges. Existing bridge railing may be modified/remounted or completely replaced with this project. Railing replacement with concrete parapet will be investigated. Approach guardrail will be replaced to meet current standards. The immediate asphalt approaches will be repaved. The existing right-of-way width is 66 feet, whereas the ultimate right-of-way width is 100 feet. The county does not anticipate purchasing the ultimate right-of-way width. However, some land acquisition is anticipated to relocate one or two driveways for guardrail construction. At construction, it is anticipated that the bridge will be closed to traffic with a detour in-place. An independent study report was completed in 2023, and application was made to WisDOT for federal funding. WisDOT did not concur with our recommended concrete overlay and the independent study report was revised using a modified scope, which was approved by WiSDOT. Though scope is modified, total project cost is reduced only slightly, mostly due to inflationary increases in the revised independent study report.

Locations: Town of Mukwonago

Analysis of Need: The existing bridge (B-67-202) is a single span flat slab structure that was constructed in 1981. The bridge wearing surface is an estimated 8% delaminated and is beginning to spall. The delamination is due to corrosion of the top mat of bar steel. The slab underside is spalled along both edges. The approach guardrail is in poor condition and does not meet current standards. The roadway is functionally classified as a 'minor arterial.' The structure sufficiency number is 59.2. This indicates that structure rehabilitation is warranted according to WisDOT guidelines, which makes the bridge eligible for federal bridge rehabilitation funding when the sufficiency index is below 80. An independent engineering study report will be prepared for this project prior to application for federal bridge funding. The purpose of the report is to verify that the proposed project scope is a cost-effective rehabilitation strategy. The 2018 traffic volume on this roadway segment was 1,200 vehicles per day.

<u>Alternatives:</u> Reconstruct the existing bridge and roadway approaches to current WisDOT standards. This alternative, while addressing the deficiencies, is not warranted.

Ongoing Operating Costs: Maintenance costs will be reduced in the early years after construction beyond 2027.

## **Previous Action:**

Approved as a new project in the 2022-2026. Approved as planned in the 2023-2027 capital plan. Approved with a cost and revenue update in the 2024-2028 capital plan.