

Project Summary – April 7, 2025

CTH EF (Hartling Road)
Bridge over Bark River B-67-210
Waukesha County
Project I.D. 2756-05-01/71

Project Overview

The existing bridge on CTH EF (Hartling Road) over the Bark River is a two-cell box culvert structure. The structure was built in 1980. The deck surface is delaminated and is beginning to spall. The ends of the box culvert is deteriorated, with surface spalling. The guardrail at the bridge is in poor condition and is sub-standard.

The project scope is bridge rehabilitation consisting of concrete deck overlay. Portions of the culvert will be repaired with concrete surface patching. Wingwall movement will be stabilized. The project will include approach paving and guardrail replacement.

The bridge will be closed to traffic during construction, with a detour posted. The Ice Trail runs north-south along the Bark River at this project site. The Ice Age Trail will be closed at the project site, with a detour posted. The project design and construction is funded using federal and county funds. Design began in 2023 and extended through 2024. Construction is anticipated to begin early July 2025 through August.

Project Schedule

Utility relocation – Spring 2025
Construction – July-August 2025

Project Contacts

Kevin Yanny, P.E.
Project Manager
Waukesha County
262-548-7740
kyanny@waukeshacounty.gov